



NOTES:

1. ALL FOUNDATION LOCATIONS SHALL BE DETERMINED IN FIELD BY TRAFFIC DIVISION AT TIME OF CONSTRUCTION.
 2. FOUNDATION TOP SHALL BE FINISHED ON ALL SIDES WITH BROOM FINISH AND EDGED WITH A 1/2" EDGER.
 3. CABINET ANCHORS ARE WEDGE ANCHORS, 4 PER CABINET, 1/2" X 4 1/2" STAINLESS STEEL (#304) FULL THREADED.
- ① 3" FROM HIGHPOINT OF FINISHED SIDEWALK GRADE, 4" FROM HIGHPOINT OF FINISHED BOULEVARD GRADE.
- ② PROVIDE PROTECTIVE BUSHINGS ON ALL CONDUITS
- ③ ELECTRICAL CONDUITS AS SPECIFIED
- ④ KEEP SERVICE FEED TO LEFT OF BARRIER
- ⑤ TWO GROUND RODS (1/2" X 8') ARE REQUIRED ON ALL SERVICE CABINETS
- ⑥ ALL DUCTS SHALL BE WITHIN RECTANGULAR OPENING

NO SCALE



DRW: EAV

DATE: 2/3/20

APP: DRP

DATE: 2/3/20

FOUNDATION - SIGNAL

CONTROLLER CABINET TYPE "P" AND ST. LIGHT / DUAL SERVICE CABINET

REFERENCE PLATE: TRAF-3500

STANDARD PLATE NO. TRAF-1071-R6